




PB99-137903



JTRP

Joint
Transportation
Research
Program

FHWA/IN/JTRP-98/11

Final Report

**Controlling Air Content in Concrete That is Being
Pumped, A Synthesis Study**

**Charles F. Scholer
Jay Grossman**

August 1998

REPRODUCED BY: **NTIS**
U.S. Department of Commerce
National Technical Information Service
Springfield, Virginia 22161

Indiana
Department
of Transportation

Purdue
University



INDOT Research

TECHNICAL *Summary*

Technology Transfer and Project Implementation Information

TRB Subject Code: 32-02 Concrete Characteristics and Tests
Publication No.: FHWA/TN/JTRP-98/11, SPR-2202

August 1998
Final Report

Controlling Air Content in Concrete That is Being Pumped, A Synthesis Study

Introduction

Changes in the intentionally entrained air content of fresh concrete that is being pumped are important to understand as this placement method continues to be widely used. Locations where a change can occur include (1) as the concrete is initially being loaded into the pump hopper, (2) as it passes

through the pump line, and (3) when it exits the line. Understanding the mechanisms which cause air loss in fresh concrete that is being pumped will allow placement crews to control adverse conditions which may be present while pumping to ensure the quality of the concrete that is placed.

Findings

The goal of this synthesis was to collect the recent findings of various researchers into a single report detailing the mechanisms by which entrained air voids are lost in concrete, and what practices help to limit this loss during pumping. Air void losses can occur in three general locations during the pumping process: as the concrete is being loaded into the pumping unit's hopper, as it travels through the pump line, and as it exits the line into the forms. Concrete traveling through the pump line can lose air content by three main mechanisms:

the high-pressure dissolution of air voids, the bursting of voids by vacuum, and the rupture of voids by impact forces. These actions occur mainly when concrete is pumped at high pressures, when it is allowed to fall freely in a pump line, and when it impacts elbows or turns at a high velocity. Impact force is also the main cause of air loss at the point of discharge from the line. If the concrete exits the pump line at a high velocity some air content may be lost when it impacts the formwork.

Implementation

To control the loss of air content in concrete that is being pumped it is important to limit the presence of the adverse mechanisms described above. Concrete should be pumped at the lowest pressure that is practical, which means that steeply rising sections of pump line should be kept to a minimum. Steeply descending sections of

pump line should also be limited to control the possible formation of a vacuum in the line. The rate of discharge and the length of drop from the end of the pump line to the formwork should be kept low to reduce the impact force acting on the fresh concrete. Extra elbows, a flexible hose section, or a reducer fitting should be employed to keep

the discharge velocity relatively low and constant. This not only limits the impact forces on the concrete as it is discharged, but will help to keep the pump line full to guard against the formation of vacuum. Care should be taken to ensure that the exit end of the pump line is not more than two feet above the level where it is to be placed, and that the concrete is not made to flow far

through the formwork after exiting the line. Laying a terminating section of flexible hose on the deck, pointing it upwards at the very end, and moving it often works well in this regard. It is strongly suggested that these items be discussed at preconstruction conferences, with the constructor identifying how their procedure will minimize the loss of air content.

Contact

For more information:

Prof. Charles F. Scholer
Principal Investigator
School of Civil Engineering
Purdue University
West Lafayette IN 47907
Phone: (765) 494-5017
Fax: (765) 496-1176

Indiana Department of Transportation
Division of Research
1205 Montgomery Street
P.O. Box 2279
West Lafayette, IN 47906
Phone: (765) 463-1521
Fax: (765) 497-1665

Purdue University
Joint Transportation Research Program
School of Civil Engineering
West Lafayette, IN 47907-1284
Phone: (765) 494-9310
Fax: (765) 496-1105

Final Report

FHWA/IN/JTRP-98/11

Controlling Air Content in Concrete That is Being Pumped, A Synthesis Study

by

Charles F. Scholer
Professor of Civil Engineering
Purdue University
West Lafayette, Indiana

and

Jay Grossman
Graduate Research Assistant
School of Civil Engineering
Purdue University
West Lafayette, Indiana

Joint Transportation Research Program
Project No: C-36-61N
File No: 5-14-14

Prepared in Cooperation with the
Indiana Department of Transportation and
the U.S. Department of Transportation
Federal Highway Administration

The contents of this report reflect the views of the authors who are responsible for the facts and the accuracy of the data presented herein. The contents do not necessarily reflect the official views or policies of the Federal Highway Administration and the Indiana Department of Transportation. This report does not constitute a standard, specification or regulation.

Purdue University
West Lafayette IN 47907
August 1998

PROTECTED UNDER INTERNATIONAL COPYRIGHT
ALL RIGHTS RESERVED.
NATIONAL TECHNICAL INFORMATION SERVICE
U.S. DEPARTMENT OF COMMERCE

1. Report No. FHWA/IN/JTRP-98/11		2. Government Accession No.		3. Recipient's Catalog No.	
4. Title and Subtitle Controlling Air Content in Concrete That is Being Pumped, A Synthesis Study				5. Report Date August 1, 1998	
				6. Performing Organization Code	
7. Author(s) Charles F. Scholer and Jay Grossman				8. Performing Organization Report No. FHWA/IN/JTRP-98/11	
9. Performing Organization Name and Address Joint Transportation Research Program 1284 Civil Engineering Building Purdue University West Lafayette, Indiana 47907-1284				10. Work Unit No.	
				11. Contract or Grant No. SPR-2202	
12. Sponsoring Agency Name and Address Indiana Department of Transportation State Office Building 100 North Senate Avenue Indianapolis, IN 46204				13. Type of Report and Period Covered Final Report	
				14. Sponsoring Agency Code	
15. Supplementary Notes Prepared in cooperation with the Indiana Department of Transportation and Federal Highway Administration.					
16. Abstract Changes in the air content of fresh concrete that is being pumped can occur at a number of places. These locations include the initial loading of the concrete into the pump hopper, as it passes through the pump line, and when it exits the line. This synthesis reviews the findings of recent research studies which deal with air content change in pumped concrete and summarizes methods of reducing air loss caused by handling. Three main mechanisms by which air content is lost in fresh concrete that is being pumped have been noted. These factors include the high-pressure dissolution of air voids, the bursting of air voids by vacuum, and the loss of air content due to impact force. Entrained air content can be retained by proper attention to the pump operation and set-up. Keeping steeply descending sections of pump line to a minimum, using kinks, elbows, or reducers at the end of the line to slow the rate of concrete flow, and pumping the concrete at the lowest pressure possible will keep air content losses to a minimum. Further beneficial actions include not allowing rain water to enter the pump's hopper, and minimizing the distance that the concrete must fall from the end of the pump line to the placement surface. Testing the air content of concrete at the point of placement will yield the most indicative results of the concrete in the finished structure.					
17. Key Words Air content, air-entrained concrete, entrained air, pumping, air voids.			18. Distribution Statement No restrictions. This document is available to the public through the National Technical Information Service, Springfield, VA 22161		
19. Security Classif. (of this report) Unclassified		20. Security Classif. (of this page) Unclassified		21. No. of Pages 12	
				22. Price	

Contents

1	Introduction.....	1
2	Changes in Air Content at Delivery	1
3	Air Losses in the Pump Line.....	2
	3.1 High Pressure Dissolution of Air Voids	2
	3.2 Bursting of Voids by Vacuum.....	3
	3.3 Impact Force.....	4
	3.4 Controlling Air Loss	4
4	Testing for Air Content	6
5	Conclusion	7
6	Implementation	7
7	Recommended Further Activity.....	8

1 Introduction

Changes in the intentionally entrained air content of fresh concrete can occur at a number of places in the pumping process. These locations include as the concrete is initially being loaded into the pump hopper, as it passes through the pump line, and when it exits the line. This synthesis reviews the findings of recent research studies which deal with air content change in pumped concrete and summarizes methods of reducing entrained air loss caused by handling.

2 Changes in Air Content at Delivery

Some change of air content in concrete being delivered to the site and loaded into the pump has been noted. Yazdani (1996) reports that, “a small amount of air appears to mix with the concrete when the concrete first enters the pump due to the pressure present in the pump line.” He further notes that:

The concrete and the pump should be protected from adverse weather. If pumping has to occur during rain, a method should be implemented to keep excess water from building up in the pump’s hopper. This water can increase the concrete air content because the excess water which does not hydrate eventually evaporates and causes air voids.

These air voids are not intentionally entrained, are not in a bubble form, and therefore do not contribute to freeze/thaw durability. Other changes in the air content may take place if the delivering trucks must wait a long time to unload. Continuous mixing of concrete containing micro-silica or fly ash may shift the void size finer, which an air meter might interpret as a loss of air content (Hover 1989).

3 Air Losses in the Pump Line

Air void losses in the pump line have been attributed to three main causes. These causes are: dissolution by high pressure, bursting due to vacuum, and mechanical rupture by impact (Yingling et al. 1992, Boulet et al. 1997).

3.1 High Pressure Dissolution of Air Voids

Boulet et al. (1997) report at length on the factors influencing the dissolution (loss in volume and number) of air voids by high pressure in the pumping process. High pressure forces the air voids in concrete to become smaller or disappear, from which they don't entirely recover when the pressure returns to lower levels. Dissolution affects the smaller air voids much more so than larger ones. These are normally the entrained bubbles needed for freeze/thaw durability. Therefore, the loss of air through this effect is potentially more detrimental to concrete durability than air lost through the vacuum or impact effect.

In the research performed by Boulet et al., when concrete was exposed to a 5.5 MPa (800 psi) pressure the number of voids decreased by a factor of 100, and all of the voids less than 100 μ m disappeared. This led to a decrease of the specific surface of the air voids as obtained from the ASTM C457 microscopical examination of the concrete. Furthermore, the ASTM spacing factor of the air voids was shown to increase linearly with pressure as the flow length increased exponentially. Normal pumping pressures rarely exceed 3.5 MPa (500 psi).

The influence of pressure was found to affect all types of concrete in the same manner. Changes in the water/cement ratio, or in the types of admixtures used did not affect the basic relationship of pressure to air loss.

Dissolution of the air bubbles was noted in the very first seconds after the concrete was subjected to pressure. The calculated spacing factor and flow length (distance excess water must travel to escape a freezing capillary pore) increased significantly in this time and then remained stable. Since this process occurs very quickly, increasing the pumping rate to reduce the time that the concrete is under pressure is not thought to be an effective means of lowering the amount of damage to the concrete's air void structure.

3.2 Bursting of Voids by Vacuum

When concrete is pumped down a descending section it may overcome the effects of friction, slide, and create a vacuum. This condition can lead the larger air voids to burst due to their internal pressure. The bursting of voids through this process can lead to significant detected air loss (Hover 1989, Yingling et al. 1992, Yazdani 1996). However, the loss of the larger air voids is reported by Boulet et al. (1997) as having little effect on the air void spacing factor.

Hover (1989) found in his study that:

The angle of the concrete pipeline had a significant and consistent effect on the loss in air content. Placing concrete close to a truck-mounted boom pump such that the concrete was first pumped up at a steep angle, and then down the far side at a steep angle, consistently resulted in a loss of 4% air

. . . When the placement had progressed so that the pump angle was nearly horizontal, air loss in pumping for the same concrete was consistently 2%.

His analysis of this phenomena was that, “pumping ‘downhill’ may result in a pressure drop in the fluid concrete in the pipeline which may favor the escape of entrained and entrapped air.”

3.3 Impact Force

Yingling et al. (1992) report that the air loss mechanism in pumped concrete may largely be the impact of rapidly moving concrete contacting stationary objects and thus breaking the internal air voids through mechanical action. It was found that a significant portion of the initial air content—20 to 40%—could be lost by the effect of impact. Other researchers have found similar results.

Hover and Phares (1996) noted from their research that:

A long vertically descending pump line is in reality a long tremie, or elephant trunk , and . . . the impact of fresh concrete on the walls, joints, and finally the deck knocks air out of the system.

From the same study they report that, “Pumping with unimpeded free-fall generally reduced air content by 0.5 to 2 percentage points.”

3.4 Controlling Air Loss

To reduce the amount of air loss in the pump line due to the three mechanisms mentioned above, a number of suggestions have been proposed. The first is to avoid pumping down

long descending sections. This will reduce the likelihood of a vacuum forming as well as limiting the impact force acting on the concrete both in the pipeline and when it exits. When pumping downward 50 feet or more, the American Concrete Institute (1996) recommends placing an air release valve in the middle of the top bend of the pump line to prevent either vacuum or air buildup.

Where descending sections are used, measures to build up resistance in the line and slow the descent of the concrete have also proven effective in controlling air loss, mainly by limiting excessive impact forces. These measures include adding 90 degree turns at the end of the line, laying the last ten to twenty feet of line horizontal, and moving the pump or boom to reduce vertical sections (Yingling et al. 1992, Hover and Phares 1996, Yazdani 1996). The Indiana Department of Transportation's Standard Specifications (1995) also limit the distance concrete being placed can be allowed to fall in open air to two feet and require a flexible end section at least ten feet long.

To avoid dissolution of air voids, the pumping pressure should be kept to a minimum. Yingling et al. (1992) reported no loss of air content in their study when concrete was being pumped horizontally at a low pressure. Boulet et al. (1997) found the highest pressures, and therefore the most damaging ones, occurred in cases where concrete was being pumped vertically through a narrow nozzle.

4 Testing for Air Content

In most situations air meters are relatively accurate in determining the air content of fresh concrete, however some discrepancies have been noted. Ozyildirim (1991) reports that:

The air content of fresh concrete measured by pressure meters and that determined by the microscopic method for essentially the same concrete after hardening are, for practical purposes, the same. The air content obtained by a volumetric meter as normally run in the field is generally lower than that obtained for the same hardened concretes by the microscopical method. . . . a higher air content in hardened concretes . . . is likely to be present if water is added during placement.

In contrast, Hover (1989) found in his case studies that, “the air pressure meter was found to significantly underestimate the air content.” He further stated that:

It has been suggested that the discrepancy between fresh and hardened air contents may be due to the inaccuracy of the pressure meter in measuring the total air content of concrete mixes with very small entrained air bubbles. It has been qualitatively proposed that the air meter becomes increasingly less accurate as the bubbles become smaller.

Testing for air content at the point of placement will obviously provide the most accurate results for determining the amount of entrained air in the final structure. As the American Concrete Institute (1996) states, “The quality of the concrete being placed in the structure can only be measured at the placement end of the line.” Some difficulties in testing at the placement point have been seen however. On this subject Hover and Phares (1996) noted the following:

To temporarily halt a bridge-deck-placing operation to deposit point-of-placement samples directly from the pump into the tester’s bucket or wheelbarrow will probably require that the pump boom, line configuration, and pumping rate be changed. For better or worse, such samples may not be representative of the concrete in the structure.

The most feasible procedure for taking fresh concrete samples should be agreed upon during the pre-construction meeting.

5 Conclusion

The change in air content of concrete that is being pumped can be attributed to three main actions. The dissolution of air voids by high pressure, the bursting of voids by vacuum, and the mechanical rupture of voids by impact forces. These detrimental actions can be controlled by keeping steeply descending sections of pump line to a minimum, using kinks and elbows at the end of the line to slow the rate of concrete flow, and to use the lowest pressure possible in the pumping operation.

The air content of concrete may also rise during the placing operation when it is remixed in the hopper prior to pumping. Rain water being allowed to enter the hopper and thereby getting mixed in with the concrete may also raise the ultimate air content.

Testing of the concrete for air content is best done at the point of placement rather than as it is loaded into the pump's hopper. The results of a test at this point will be the most indicative of the concrete in the structure, but may not be an exact match due to changes in the pumping configuration needed to acquire the sample.

6 Implementation

The implementation of best construction practices should be discussed in detail at the pre-construction conferences in which the three main mechanisms of air void loss are explained. The constructor should have the opportunity at these meetings to describe

how they will minimize these effects, and agreement reached on the practice which will be followed in the field. Proper freeze/thaw durability is essential in nearly all highway applications and should not be sacrificed for a construction expediency such as using higher slumps for easier placement.

The procedure for air content testing should also be discussed and agreed upon at the pre-construction conferences. Special emphasis should be given to where the sample will be taken, and what standard procedures will be followed during the testing (e.g. method of consolidation).

7 Recommended Further Activity

It is recommended that a short instructional video be prepared to cover the primary points of this synthesis and the accepted practices for concrete placement. It is further suggested that a number of pre-construction or pre-bid conferences be attended to gather information on what types of questions are of the most concern to constructors in relation to the proper placement of fresh concrete.

References

- American Concrete Institute. 1996. *Construction Practices and Inspection, Pavements*. Part 2 of *ACI Manual of Concrete Practice*. Farmington Hills: American Concrete Institute.
- Boulet, Daniel, Richard Pleau, Pierre-Claude Aïtcin, and Michel Lessard. 1997. Influence of Pumping on the Characteristics of the Air-Void System of Concrete. Annual Conference of the Canadian Society for Civil Engineering, 27-30 May, Sherbrooke, Quebec.
- Hover, Kenneth C. 1989. Some Recent Problems with Air-Entrained Concrete. *Cement, Concrete, and Aggregates* 11, no. 1: 67-72.
- Hover, Kenneth C., and Roger J. Phares. 1996. Impact of Concrete Placing Method on Air Content, Air-Void System Parameters, and Freeze-Thaw Durability. *Transportation Research Record* 1532. TRB, National Research Council. Washington D.C.
- Indiana Department of Transportation. 1995. *Standard Specifications*. Indianapolis: Indiana Department of Transportation.
- Khayat, Kamal H., and Karim W. Nasser. 1991. Comparison of Air Contents in Fresh and Hardened Concretes Using Different Airmeters. *Cement, Concrete, and Aggregates* 13, no. 1: 18-24.
- Ozyildirim, Celik. 1991. Comparison of the Air Contents of Freshly Mixed and Hardened Concretes. *Cement, Concrete, and Aggregates* 13, no. 1: 11-17.
- Roberts, Lawrence R. 1994. Air Content, Temperature, Unit Weight, and Yield. In *Significance of Tests and Properties of Concrete and Concrete-Making Materials*, ed. Paul Klieger and Joseph F. Lamond. American Society for Testing and Materials Special Technical Publication 169C. Fredericksburg.
- Whiting, D., and D. Stark. 1983. Control of Air Content in Concrete. *National Cooperative Highway Research Program Report no.258*. TRB, National Research Council. Washington D.C.
- Yazdani, Nur. 1996. *Effect of Pumping on Properties of Concrete*. Florida Department of Transportation/FAMU-FSU College of Engineering. Tallahassee.
- Yingling, James, Gary M. Mullings, and Richard D. Gaynor. 1992. Loss of Air Content in Pumped Concrete. *Concrete International* 14, no. 10: 57-61.

